

Fermilab E-906/SeaQuest Installation Update

Paul E. Reimer
8 March 2010

1. Progress we've made
2. Plans for run
3. What needs to be done

Slides with help from the collaboration

Progress: NM4 Hall

Cleanout—essentially done Dec. 2009

- KTeV detectors have been removed from the region needed for E906
 - Cable trays; KTeV cables need attention
 - Still some KTeV “junk” to be remove for adequate auxiliary working areas
- Resurvey of the NM4 Hall primary survey has been completed

Installation

- K MAG magnet moved to new position.
- Beam height raised from 95” to 95.5”
- Base blocks and first Fe layer of FMAG installed
- Station 2 frame moved in place, Station
- 2 drift chambers are now in place.
- Power bus extended to both magnets

Much thanks to Fermilab support!



Progress: Wire Chamber Repairs

E-866/NuSea Station 2


- Will become bottom half of E906 Station 3
- 3 chambers – U/U' , Y/Y' , V/V' , 6 planes, 1 cm wire spacing, 1184 sense wires, 148 8-channel cards, 67" by 64" active area
- 5 of 6 planes had some broken wires
- Repaired in Lab 6 by Lamiaa, Kenichi, Shou, Dave Northacker, and Wanda Newby (a Fermilab tech); all now OK !!
- Took about 3 weeks to repair about 50 broken wires

E-866/NuSea Station 3


- Will be E-906 St. 2
- Up next in Lab. 6 (opened this afternoon)



Progress: Wire Chamber Repairs



Paul E. Reimer, E-906/SeaQuest, Fermilab AEM



Other Spectrometer Progress

- Hodoscope St. 1 & 2
 - HERMES Scint. Recutting at UIUC now
 - PMT testing at UIUC now
- Hodoscope St. 3 & 4
 - St. 4 Scint. Wrapped;
 - St. 3 ordered.
 - Approx . 2/3^{rds} of PMT' s tested
- Tracking St. 1
 - Design in progress
 - **Ready for Post-summer shutdown**
- Tracking St. 2
 - Old E-866 Chambers
 - 1st one opened in Lab 6 today!
- Tracking St. 3+
 - Fabricated in Japan
 - Ships 1 April 2010
- Tracking St. 3-
 - Reconditioned in Lab 6
 - Gas Leak Checking
- Tracking St. 4
 - Prop. Tubes delivered to NM4
 - Testing underway
- Cryotargets
 - Cooldown tests at Michigan (1 cryocooler passed, 1 failed)
 - Motion table reconditioned
 - **Ready for Post-summer shutdown.**
- Electronics
 - Prototypes in testing
- Software
 - Data storage and decoding underway
 - Pattern recognition underway

The Plan

Ready for commissioning beam on 21 June 2010—before summer shutdown starting on 19 July 2010

- Goal:

- Determine actual trigger and background rates
- Exercise entire event chain

Chamber->electronics->DAQ->data storage->decoding->reconstruction

- Expected Equipment

- All Hodoscopes
- Trigger
- St. 4 Prop. Tubes (In NM4 almost ready to mount)
- St. 3+ Tracking Chamber (to be shipped from Japan in April)
- St. 3- Tracking Chamber (successfully reconditioned, but needs gas leak check)
- St. 2 Tracking Chamber (still needs repair—started today)
- Associated electronics (Prototypes being tested)
- DAQ
- Solid Target

- **Beam Line** (Schedule under Fermilab control—not under collaboration control)

Needed to Achieve the Plan

- Continued cooperation with the chamber repairs (so far, **this has been excellent!**)
- Continued work on the magnet assembly (again, **this has been excellent so far!**)
- Mechanical support for spectrometers
- Additional space in KTeV Hall, now used for tape storage.
- Start on Safety Reviews— *the collaboration takes this seriously and recognizes that this will encompass significant effort for both the collaboration and Fermilab staff*
 - Mechanical
 - Electrical
 - Cryogenic
 - Chamber gas systems

Please bear with us (me) as we (I) may be naïve about the process and ask questions that are apparently obvious.
- **Engineering and technical support for beam line** (*we are told the lack of engineering and mechanical tech effort in the AD may slow down work on the beam line*)